Notification No. L. F2. C.—33-34, *dated 9th February* 1934.

Notice is hereby given that sealed tenders will be received at the Office of the President, Local Education Authority, and District Board, Tumkur, up to 12 noon on 7th March 1934, for Constructing the Primary School Building between Gondihalli and Halethimmanah alli, Madhugiri Taluk. An approximate estimate of quantities is given below. The work sho uld be completed by the end of December 1934.

2. The plan, detailed estimate and conditions may be seen at the abovementioned office between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the President Local Education Authority and District Board, Tumkur. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred (Rs. 100) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Constructing the Primary School Building between Gondihalli and Halethimmanahalli, Madhugiri Taluk" in default of which, tenders will be rejected.

5. The final acceptance of the tender will rest with the President, Local Education Authority, and District Board, Tumkur, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the President's Office of the Local Education Authority in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8 On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The rates should be written legibly both in figures and words without correction.

10. The contractor will not be allowed to claim enhanced rates after the submission of the tender at any stage.

11. The decision of the President, Local Education Authority, and District Board, Tumkur, will be final and legally binding on the contractor in case of disputes about the rates, qualities and quantities of work.

Abstract of the estimate.

Sl. No.	Items of work	Quantity	Per Rate
1	Earthwork excavation for foundation ...	27	C.yds.
2	Jelly concrete in mortar for foundation ...	145	C.ft.
3	Foundation burnt stone in clay ...	721	,,
4	Superstructure burnt brick in clay ...	573	,,
5	Brick honey comb work with chunam plastering ...	256	S.ft.
6	Burnt stone slabs 6" thick roughly dressed ...	62	,,
7	Chunam plastering ...	14·98	Sqr.
8	Chunam pointing basement ...	1·63	,,
9	White washing ...	14·98	,,
10	Junglewood work Neem or Margosa wrought and put up.	135	C.ft.
11	Teakwood battened doors with shutters, etc, complete...	46	S.ft.
12	Do windows with shutters, iron bars, etc.	60	,,
13	Roofing with first Class Mangalore tiles on teak reepers including fixing and wood oiling to reepers.	14·10	Sqr.
14	Ridge tiles set in mortar ...	100	R.ft.
15	Filling up the basement and tamping with gravel...	28	C.yds.
16	Flooring with Cuddapah slabs over 3" thick concrete and cement pointing.	5·10	Sqr.
17	Chocolate painting to doors and windows ...	2·12	,,
18	Tarring to wood work ..	Lump sum	
19	For unforeseen works ...	Lump sum	

Notification No. L. F2-C.—33-34, dated 9th February 1934.

Notice is hereby given that sealed tenders will be received at the Office of the President, Local Education Authority and District Board, Tumkur, up to 12 noon on 7th March 1934, for constructing the Primary School Building at Channakesavapura, Pavagada Taluk. An approximate estimate of quantities is given below. The work should be completed by the end of December 1934.

2. The plan, detailed estimate and conditions may be seen at the abovementioned Office, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the President, Local Education Authority and District Board, Tumkur. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees one hundred in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for constructing the Primary School at Channakesavapura, Pavagada Taluk", in default of which, tenders will be rejected.

5. The final acceptance of the tender will rest with the President, Local Education Authority and District Board, Tumkur, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the President's Office of the Local Education Authority in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The rates should be written legibly both in figures and words without correction.

10. The contractor will not be allowed to claim enhanced rates after the submission of the tender at any stage.

11. The decision of the President, Local Education Authority and District Board Tumkur, will be final and legally binding on the contractor in case of disputes about the rates, qualities and quantities of work.

Abstract of the estimate.

Sl. No.	Items of work	Quantity	Per Rate
1	Earthwork excavatiou for foundation ...	27	C.yds.
2	Jelly concrete in mortar for foundation ...	145	C.ft.
3	Foundation burnt stone in clay	721	,,
4	Superstructure burnt brick in clay ...	573	,,
5	Brick honey comb work with chunam plastering ...	256	S.ft.
6	Burnt stone slabs 6" thick roughly dressed ...	32	,,
7	Chunam plastering ...	14·98	Sqr.
8	Do pointing basement ...	1·63	,,
9	Wite washing ..	14·98	,,
10	Junglewood work, Neem or Margosa wrought and put up.	135	C.ft.
11	Teakwood battened doors with shutters, etc., complete.	46	S.ft.
12	Do windows with shutters, iron bars, etc.	60	,,
13	Roofing with First Class Mangalore tiles on teak reepers including fixing and wood oiling to reepers.	14·10	Sqr.
14	Ridge tiles set in mortar ...	100	R.ft.
15	Filling up the basement and tamping with gravel..	28	C.yds.
16	Flooring with Cuddapah slabs over 3" thick concrete and cement pointing.	5·10	Sqr.
17	Chocolate painting to doors and windows ...	2·12	,,
18	Tarring to wood work ...	Lump sum	
19	For unforeseen works ...	Lump sum	

H. VENKATARAMAIYA,
President,
Local Education Authority.